

VERSION: V3.0

DATE PUBLISHED: 06/20/23

DEFINITION:	A vertical	A vertical structure that retains soil or rock at various grades. To prevent erosion on sloped land or to add usable space.					
PURPOSE:	To prever						
COMMON COMPONENTS:	Post; Rail	ing; Block					
LOCATION:		Unit	None				
		Inside	None				
	\boxtimes	Outside	Property grounds				
MORE INFORMATION:		•	is inspection, a "retaining wall" is only classified as such if it is at least 24 inches tall and does not ters or foundation wall.				
DEFICIENCY 1: Location:	Retaining wal 🔀 Outside	l is leaning a	way from the fill side.				
DEFICIENCY 2: LOCATION:	Retaining wal	l is partially (or completely collapsed.				



Deficiency I = Outside: Retaining wall is leaning away from the fill side.

Deficiency Criteria:	Retaining wall is leaning away from the fill side.			
Health and Safety Determination:	Moderate	The Moderate Health and Safety category includes deficiencies that, if evident in the home of on the property, present a moderate risk of an adverse medical event requiring a healthcar visit; cause temporary harm; or if left untreated, cause or worsen a chronic condition that ma have long-lasting adverse health effects; or that the physical security or safety of a resident o their property could be compromised.		
Correction Timeframe:	30 days			
HCV Pass / Fail:	Fail			
HCV CORRECTION TIMEFRAME:	30 days			
Inspection Process:				
Observation:	- Look at the retaining wall while standing parallel to determine if the wall is standing upright. - Verify the wall is not more than 90 degrees from the base of the slope.			
REQUEST FOR HELP:	- None			
Action:	- Measure the retaining wall to verify the height is 24 inches or greater. - If it is not at least 24 inches, then it is not subject to inspection.			
More Information:	- If the retaining wall is leaning (sloped) toward the fill side, do not cite a deficiency. - If present, inspect the guardrail under the Guardrail standard.			



DEFICIENCY 2 - OUTSIDE: RETAINING WALL IS PARTIALLY OR COMPLETELY COLLAPSED.

DEFICIENCY CRITERIA:	Retaining wall is partially or completely collapsed.			
Health and Safety Determination:	Moderate	The Moderate Health and Safety category includes deficiencies that, if evident in the home or on the property, present a moderate risk of an adverse medical event requiring a healthcare visit; cause temporary harm; or if left untreated, cause or worsen a chronic condition that may have long-lasting adverse health effects; or that the physical security or safety of a resident or their property could be compromised.		
Correction Timeframe:	30 days			
HCV Pass / Fail:	Fail			
HCV CORRECTION TIMEFRAME:	30 days			
Inspection Process:				
OBSERVATION:	- Look at the entire retaining wall for signs of collapse.			
R EQUEST FOR HELP:	- None			
Action:	- None			
More Information:	- None			